BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE, BYATRAYANAPURA DIVISION

Name of the work: **Improvements to roads and drains of BB Nagara in ward no. 8 kodigehalli**

			Estimate Cost: Rs.						7500000.00
Sl. No	Description	Unit	No.	L	B	D	Qty	Rate	Amount
1	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its qualityf 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction (P.47, I. 9.4) PRED.SR 2012-13								
	Basic Rate	1882.00							
	Area Weightage 3%	56.46							
	Total	1938.46							
		Each	1				1.00	1938.46	1938.00
2	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) Page no. 46 / I. 9.1 PRED SR 2012-13								
	Basic Rate	306.00							
	Area Weightage 3%	9.18							
	Total	315.18							
	0 to 50 m	Rm	1	50.00			50.00	315.18	15759.00
3	Basic Rate	400.00							
	Area Weightage 3%	12.00							
	Total	412.00							
	50 to 100 m	Rm	1	50.00			50.00	412.00	20600.00
4	Basic Rate	445.00							
	Area Weightage 3%	13.35							
	Total	458.35							
	100 to 150 m	Rm	1	50.00			50.00	458.35	22918.00
5	Basic Rate	470.00							
	Area Weightage 3%	14.10							
	Total	484.10							
	150 to 200 m	Rm	1	50.00			50.00	484.10	24205.00
6	Basic Rate	544.00							
	Area Weightage 3%	16.32							
	Total	560.32							
	200 to 250 m	Rm	1	50.00			50.00	560.32	28016.00
7	Basic Rate	583.00							
	Area Weightage 3%	17.49							
	Total	600.49							
	251 to 300 m	Rm	1	50.00			50.00	600.49	30025.00
8	Basic Rate	622.00							
	Area Weightage 3%	18.66							
	Total	640.66							
	300 to 350 m	Rm	1	50.00			50.00	640.66	32033.00

	Description	Unit	No.	L	B	D	Qty	Rate	Amount
9	Basic Rate	677.74							
	Area Weightage 3%	20.33							
	Total	698.07							
	350 to 375 m	Rm	1	25.00			25.00	698.07	17452.00
10	Supply of ISI mark 175 mm nominal bore medium black ERW casing pipe of 5 mm thick black electric resistance continuous welded mild steel tube material confirming to IS 1387 / 1993 & manufactured from hot rolled steel skelp / stripes in random length of 4 to 7 mts both ends threaded confirming to IS 554 / 1985, one end fixed with a socket and the other and with a plastic protection end (including of all taxes) SE PRED III NO 84								
		Rm	1	54.00			54.00	1325.00	71550.00
11	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials, labour charges, HOM of acquirements and testing complete as per specifications. - 250mm dias. (Page No. 90, Item No. 12.116.5, PWD SR 2018-19)								
	Basic Rate	2052.00							
	Area Weightage 6%	123.12							
	Total	2175.12							
		Rm	1	12.00			12.00	2175.12	26101.00
12	Providing MS Casing pipe collars page no III it no 86 pred 12-13 sr								
		No.	1	9			9.00	150.00	1350.00
13	Providing 175mm dia ms casing cap page no III it no 85 pred 12-13 sr								
		No.	1				1.00	100.00	100.00
14	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings. (Sl No. 49, Page No. XLII, PWDSR 2018-19)								
	17.5 HP 30 Stage	Unit	1				1.00	72126.00	72126.00
15	KSRB13-3.1: Providing and fixing to wall celling and floor glavanised/ mild steel tubes (medium grade 1.27 kg /mt) B class 50 mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. (Page 92, Item No 13.6, PWDSR 2018-19)								
	Basic rate	512.00							
	6% AW	30.72							
	Sub Total	542.72							
		Rm	1	320.0			320.00	542.72	173670.00
16	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and Powder coated extrued PVC sheathed suitable for working voltage upto 1100 Volts as per IS - 694 ; 1990 AND CONFORMING TO gtp OFGROUP A P. No. 12/ I No. (2.10.4) 3cx 6.0 Sqm KPWD								
		Rm	1	640.00			640.00	188.70	120768.00
17	Labour charges for erection of new / repaired submersible pumpset along with gi pipes inculding transportion each length pno 558 ino 3 bwssb sr 14-15								
		No.	1	50.00			50.00	88.00	4400.00

	Description	Unit	No.	L	B	D	Qty	Rate	Amount
18	Supplying and flush polished wood board with out front frount plank made of not less than 15mm thick plank after due groove cutting Finishing with necessary on fixing the same to the wall using tapered inverted wooden plugs screws etc., P No. 44No.6.6.6 KPWD Electrical SR 2014-15								
	20x20x2.5	Each	1				1.00	302.00	302.00
19	Supplying of 1.1 KV LT UG cable having aluminium condutor PVC insulated shethed, EXTRUDED INNER SHEATHRD galvnised steel,stirp confirming IS 3975;1990 AND extruded PVC outer sheathing armoured cable IS 1554 part 1;1998 and confirming to GTP of group.P No.55/ I No.7.4.4 (4 core 16 Sqmm) KPWD Electrical SR 2014-15								
		Rm	1	35.00			35.00	140.40	4914.00
20	Labour charges for laying of 1.1 K.V class UG cable, P No. 61 / I No. 7.8.1 In existing trencg/duct 6Sqmm to 16 Sqmm) KPWD Electrical SR 2014-15								
		Rm	1	35.00			35.00	10.80	378.00
21	Digging or trenching of 0.6m deep x 0.5 mtr wide refilling the trench to the required ground level and consolidating etc., completeP No. 62/ I. No.7.9.4 KPWD Electrical SR 2014-15								
	For Cutting Road Surface aspalt	Rm	1	30.00			30.00	117.00	3510.00
22	Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class P. No. 62/ I No.7.12.1 KPWD Electrical SR 2014-15								
	40mm dia GI pipe	Rm	1	3.00			3.00	345.00	1035.00
23	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., P. No.62/ I No. 7.13.2 KPWD Electrical SR 2014-15								
	16Sqmm	No.	1				1.00	280.00	280.00
24	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipments on the meter board using 40 mm dia 2.90 mm thick GI pipe 2.5 m long buried in a pit. The pit should be filled with equal propotion of solt and charocoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size, as per ISI specification 7.3.3 IS 732 using 12 mm dia bolts, nuts, washers and check nuts, etc., the pipe shall have 16 throught holes of 122 mm dia, (P No.55, I No. 7.1) KPWD Electrical SR 2014-15								
		No.	1				1.00	2727.00	2727.00
25	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... P No44/I No 6.7.4 KPWD Electrical SR 2014-15								
	100 Amps								
		Each	1	3			3.00	360.00	1080.00
26	Supplying and fixing of heavy duty glands for ug cable 1.1 kv etc., complete.... P No62 I No 7.14.2 KPWD Electrical SR 2014-15								
	25mm dia								
		Each	1	6			6.00	86.00	516.00
27	Supplying and fixing miniature circuit breakers/solaters on existing MCB distribution boards using necessary fixing materiasl wiring complete as requireds 5 to 32 amps triple pole with all lead and lift, loading, unloading and labour charges etc complete as per specifications pno 47 IT 6.16.5 KPWD Electrical SR 2014-15								
		Each	1				1.00	1547.00	1547.00

	Description	Unit	No.	L	B	D	Qty	Rate	Amount
	Fabrication supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sqcm @ Rs.0.33 P.No. 49, I. No.6.40.2 KPWD Electrical SR 2014-15								
	16SWG	Sqmm	2	220.00	60.00		26400		
		Sqmm	1	450.00	25.00		11250		
		Sqmm					37650	0.33	12425.00
29	KSRB 13-7.1-4: Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications NO KBS 13.2.16 / 13.13 (Page No.97 Item No. 13.81.3, PWD SR 2018-19)								
	Basic rate	1330.00							
	6% AW	79.80							
	Sub Total	1409.80							
		Each	1				1.00	1409.80	1410.00
30	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete. (P. No.97, I. No. 13.81.3 PWD SR 2018-19)								
	Basic rate	210.00							
	6% AW	12.60							
	Sub Total	222.60							
	50mm dia	No.	1	2.00			2.00	222.60	445.00
31	Gate value 50 mm nominal bore gun metal (P. No.XXVI Sl No. 661 PWD SR 2018-19)								
	50mm dia	No.	1	3.00			3.00	1398.31	4195.00
32	Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shines/Adarsh/ GK Controls best indigenous make combined energy meter - cum- control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3 ph, 50Hz, 380/440 volts, A.C supply with spring loaded latch, locking device with a key ribs should be provided inside the door, canopy apron and louvers ventilators shall be provided. the combined energy meter cum- control panel board unit suitable for operation. The panel board shall be fabricated on single unit in the above components for suitable pumpset. PRED Bangalore Circle SE Approved Date [illegible]								
		No.	1				1	10000.00	10000.00
33	Earth work excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches, 1.5m and above in width, in ordinary soil, exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with all lead upto 50m after breaking of clods complete as per specifications.(P.No.6, I.No.2.1, PWD SR 2018-19)								
	Basic rate	249.00							
	6% AW	14.94							
	Sub Total	263.94							
		cum	1	50.00	0.75	0.90	33.75		
		cum					33.75	263.94	8908.00
34	KSRRB M2100-9. Sand Filling in Foundation Trenches as per Drawing & Technical SpecificationMORTH Specification No. 304. (PWDSR 2018-19, P.7, I.2.13)								
	Basic rate	2060.00							
	6% AW	123.60							
	Sub Total	2183.60							
		cum	1	50.00	0.75	0.15	5.63		
		cum					5.63	2183.60	12283.00

	Description	Unit	No.	L	B	D	Qty	Rate	Amount
	KSRB13-9.3 : Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure 50mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.15.2 / 13.9 (Page no.96, Item No.13.73.1, PWD SR 2018-19)								
		Rm	1	50.00			50.00		
	Basic Rate	235.00					50.00	249.10	12455.00
	Area Weightage @ 6%	14.10							
	Total	249.10							
36	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications. (Page No.6, Item No. 2.11 PWD SR 2018-19)								
	Basic rate	76.00							
	6% AW	4.56							
	Sub Total	80.56							
	From Pipe line excavation	cum					33.75		
	Deduct from item no. 33	cum					-5.63		
		cum					28.13	80.56	2266.00
37	BESCOM Deposit	L/S	1				1	13000.00	13000.00
38	KSRRB 300-2 : Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3 (Page No. 143, Item No. 19.2, PWDSR 2018-19)								
	RCC drain	Cum				av.			
	Maruthinagara main Road to AMCO layout Main Road	Cum	1	456.00	0.90	1.20	492.48		
	Culvert								
	Maruthinagara main Road to AMCO layout Main Road	Cum	8	6.20	1.50	1.25	93.00		
	CC road				av.				
	BB keri link road	Cum	1	81.00	5.50	0.30	133.65		
	link roads	Cum	2	30.00	4.00	0.30	72.00		
		Cum					791.13	189.74	150109.00
	Basic Rate	179.00							
	Area Weightage @ 6%	10.74							
	Total	189.74							
39	KSRB 2.8: Providing and filling in foundation with granite / trap broken metal 100mm, and downsize and with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all leaed and lift.,, complete as per specfications (Page No. 7, Item No. 2.15 PWDSR 2018-19)								
	RCC drain								
	Maruthinagara main Road to AMCO layout Main Road	Cum	1	456.00	0.90	0.15	61.56		
	Culvert								
	Maruthinagara main Road to AMCO layout Main Road	Cum	8	6.2	1.5	0.15	11.16		
		Cum					72.72	2574.74	187235.00
	Basic Rate	2429.00							
	Area Weightage @ 6%	145.74							
	Total	2574.74							

	Description	Unit	No.	L	B	D	Qty	Rate	Amount
	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (Page No. 13, Item No. 4.3, PWDSR 2018-19)								
	RCC drain								
	Maruthinagara main Road to AMCO layout Main Road	Cum	1	456.00	0.90	0.15	61.56		
	Culvert								
	Maruthinagara main Road to AMCO layout Main Road	Cum	8	6.2	1.5	0.15	11.16		
	CC road	Cum							
	BB keri link road	Cum	1	81.00	5.50	0.15	66.82		
	link roads	Cum	2	30.00	4.00	0.15	36.00		
	for pipeline refilled work	Cum	1	50.00	0.75	0.15	5.62		
		Cum					181.16	5408.12	979735.00
	Basic Rate	5102.00							
	Area Weightage @ 6%	306.12							
	Total	5408.12							
41	KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (Page No.15, Item No. 4.31, PWD SR 2018-19)								
	Maruthinagara main Road to AMCO layout Main Road	Sqm	2	456.00		0.750	684.00		
	Culvert								
	Maruthinagara main Road to AMCO layout Main Road	Sqm	16	6.2		0.75	74.40		
	Total						758.40	379.48	287798.00
	Basic Rate	358.00							
	Area Weightage @ 6%	21.48							
	Total	379.48							
42	KSRB 4.9.2: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 (Page No. 19, Item No. 4.46.2, PWD SR 2018-19)								
	For Drain	Cum	From item no.				164.16		
		kg	Steel assumed 60Kg/Cum of				9849.60		
		tonne					**9.85**		
	For Culvert	Cum	From item no.				29.76		
		kg	Steel assumed 90Kg/Cum of Concrete				2678.40		
		tonne					**2.68**		
	Total	Tonne					12.53	75255.76	942804.16
	Basic Rate	70996.00							
	Area Weightage @ 6%	4259.76							
	Total	75255.76							

	Description	Unit	No.	L	B	D	Qty	Rate	Amount
	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams. (Page No. 18, Item No. 4.49.1, PWD SR 2018-19)								
	RCC drain								
	bottom portion								
	Maruthinagara main Road to AMCO layout Main Road	cum	1	456.00	0.90	0.15	61.56		
	Side walls								
	Maruthinagara main Road to AMCO layout Main Road	cum	2	456.00	0.15	0.750	102.60		
	Culvert								
	bottom portion								
	Maruthinagara main Road to AMCO layout Main Road	Cum	8	6.2	1.5	0.2	14.88		
	Side walls								
	Maruthinagara main Road to AMCO layout Main Road	Cum	16	6.2	0.2	0.75	14.88		
	Total						193.92	5770.64	1119043.00
	Basic Rate	5444.00							
	Area Weightage @ 6%	326.64							
	Total	5770.64							
44	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)								
	Drain Cover Slab								
	Maruthinagara main Road to AMCO layout Main Road	Sqm	1	319.20	0.90		287.28		
							287.28	2337.00	671373.0

	Description	Unit	No.	L	B	D	Qty	Rate	Amount
	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, maching mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications. - 200 mm thick (Approved data rate enclosed)								
	Culvert								
	Maruthinagara main Road to AMCO layout Main Road	Sqm	8	6.2	1.5		74.40		
							74.40	5300.0	394320.0
46	Providing granite slabs of selected quality roughly dressed havinf a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete.								
	Drain Cover Slab								
	Maruthinagara main Road to AMCO layout Main Road	Sqm	1	136.80	0.90		123.12		
							123.12	966.7	119022.6
	Basic Rate	912.00							
	Area Weightage @ 6%	54.72							
	Total	966.72							
47	KSRB- 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2. (Page No. 13, Item No. 4.5, PWD SR 2018-19)								
	CC road								
	BB keri link road	Cum	1	81.00	5.50	0.15	66.82		
	link roads	Cum	2	30.00	4.00	0.15	36.00		
	for pipeline refilled work	Cum	1	50.00	0.75	0.15	5.62		
		Cum					108.44	5647.68	612434.00
	Basic Rate	5328.00							
	Area Weightage @ 6%	319.68							
	Total	5647.68							
48	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift. (Page No. 176, Item No. 22.7, PWD SR 2018-19)								
	BB keri link road	Sqm	1	81.00	5.50		445.50		
	link roads	Sqm	2	30.00	4.00		240.00		
		Sqm					685.50	72.08	49411.00
	Basic Rate	68.00							
	Area Weightage @ 6%	4.08							
	Total	72.08							
49	Providing groove cutting for width of 5mm to 10mm and depth 80mm -100mm including cost of cutting machine , generater &HOM of machinery ,including cost of blade , coolant etc ., including cleaning of groove &providing sand and hot bitumen fillars and filler metal etc., including cost of conveyance of all materials , labour lead and lift charges and all other incident charges as per drawing. (Page No. 176, I. 22.8.1, PWDSR 2018-19)								
1	BB keri link road	Rm	3	5.50			16.50		
2	link roads	Rm	1	4.00			8.00		
							24.50	143.10	3506.00
	Basic Rate Rs	135.00							
	Area Weightage @ 6%	8.10							
	Total	143.10							

Sl. No	Description	Unit	No.	L	B	D	Qty	Rate	Amount
48	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123)								
	Qty at 85% of item no. 4	Cum	0.85	528.22		672.46	448.98		
	Total			791.13		672.46	448.98	87.56	39311.00
	Basic rate for haulage of materials as per item no.17.4 page 136) Rs. 2.00								
	Average weight of earth 1.28 tonne / kg for 2.00X1.28X10.00	25.60							
	Add loading and unloading Vide item no.17.1 P.no.134	57.00							
		82.60							
	Area Weightage @ 6%	4.96							
	Total	87.56							
49	Sub Total-1								6463269.0
50	Add KRIDL charges at 3% and 1% for Labour cess (of sub total-1)							253291	258531.0
	DPR Charges (1% of Estimate Cost)								75000
51	Add GST charges @ 12% of sub total-1							759883	775592.0
	PROJECT MANAGEMENT AND CONSULTANCY CHARGES (1% of Estimate Cost)								75000
52	Miscellaneous & Rounding off							L/S	2608.00
	Total Rs								7500000.00
	Rupees Seventy Five Lakhs Only								

CERTIFICATE:

1 The work spot has been inspected and the work is found necessary.
2 This estimate is prepared as per P.W.D S.R of 2018-19
3 The provisions were made in this estimate are necessary and adequate.
4 This works come under B.B.M.P. limits.
5 This work has not been taken previously under any other grant.

Assistant Engineer
Ward no. 8
Kodigehalli

Assistant Executive Engineer
Kodigehalli Sub Division
BBMP

Executive Engineer
Byatrayanapura Division
BBMP
18/10

ADMINISTRATIVE APPROVAL

Accorded For Rs. 75.00 Seventy five lakhs only
Head of A/c P3727, SC-SP TSP
C.V. Ref. No. 71 19-20 Date 24-10-19

24/10
EE(BTP) 24/10

Technical sanction
Accorded for Rs 75 lakhs only
Head of A/c P3727
CER NO :155 28.10.2019

LTA
CE (YNK)